

**Name of Work:-Repairing of 62.5 KVA DG Set at Employees Provident Fund Organisation at Agra.**

S.NO.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE	AMOUNT	REMARKS
	SUB-HEAD-I(Repairing of DG Set)					
1.	Repairing, servicing & overhauling of 62.5 KVA DG Set(Engine make R.B. 66 FE SR-11) i/c dismantling of all defective parts as per list enclosed, providing and fixing new parts, making proper adjustment, servicing of radiator, crank shaft grinding and liner at workshop, refilling the engine oil and commissioning the whole system as per complete satisfaction of engineer-in-charge, running testing operation of DG Set 8 hours continuous on load (maximum available load) List of defective parts as under:-	1 Job	Job			
	SUB-HEAD-II (ELECTRICAL)					
1.	Supplying & fixing of 100 Amp. On load changeover switch with sheet steel enclosure side operated directly on wall with angle iron base support, making existing cable connection, testing i/c dismantling the existing defective changeover switch	1 No.	Each			

**Executive Engineer (E)-I**